





NOZZLE SCHEDULE												
ITEM	SIZE	RATING	TYPE	MATL.	PROJ. IN	PROJ. OUT	REMARKS					
Α	4''	N.P.T.	W.F.	C.S.	STD.	STD.	PRIMARY EMERGENCY VENT OPENING					
В	4''	N.P.T.	W.F.	C.S.	STD.	STD.	SECONDARY EMERGENCY VENT OPENING					
С	2"	N.P.T.	W.F.	C.S.	STD.	STD.						









NOTES:

- MATERIAL: H.R. CARBON STEEL Α.
- DESIGN & OPERATING PRESSURE: ATMOSPHERIC. DESIGN & OPERATING TEMPERATURE: AMBIENT.
- D.
- TANK TO BE BUILT & LABELED PER U.L. SPEC. #142. TANK TO BEAR MANUFACTURERS & U.L. LABELS ONLY.
- TANK TO BE AIR TESTED WITH WATER & SOAP SUDS SOLUTION.
- INTERIOR: REMOVE WELD SLAG (SHIP CLEAN & DRY).
- EXTERIOR: GRAY PRIMER INCLUDED; SEE SALES ORDER FOR TOP COAT.
- ALL FITTINGS TO BE PROTECTED FOR SHIPMENT.
- CUSTOMER HAS THE RESPONSIBILITY TO VERIFY ALL DIMENSIONS.

APPROVAL FOR CONSTRUCTION SCHEDULE A - MASTER TERMS & CONDITION OF SALE*
APPROVED AS DRAWN.
APPROVED WITH NOTED CHANGES, CONSTRUCTION WILL BE SCHEDULED

WHEN SIGNED DRAWING AND CONFIRMED ORDER ARE RECEIVED.

*All pages of this Schedule A are incorporated by reference and are a part of the additional terms of the Master Terms & Conditions of Sale. www.newberrytanks.com/masterterms.pdf

SALES	ORDER:	WEIGHT (LBS):691								
(-)		All units inches unless stated								
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	New Thinking									
Phone: 870-735-4473										
DESCRIPTION:										
280 GALLON RECTANGULAR UL 142 DOUBLE WALL TANK										
CUSTOMER:		P.O.#								
DATE: 3/7/2023	SCALE:	DWG.# FTDBS-0280		DRAWN BY:	AJC					

CHKD BY