





	NOZZLE SCHEDULE								
ITEM	SIZE	RATING	TYPE	MATL	PROJ IN	PROJ OUT	REMARKS		
Α	3''	N.P.T.	W.F.	C.S.	STD.	STD.	EMERGENCY VENT OPENING		
В	2''	N.P.T.	W.F.	C.S.	STD.	STD.			
С	3/4"	N.P.T.	W.F.	C.S.	STD.	STD.	DRAIN		









## NOTES:

- MATERIAL: H.R. CARBON STEEL Α.
- DESIGN & OPERATING PRESSURE: ATMOSPHERIC.
- DESIGN & OPERATING TEMPERATURE: AMBIENT.
- D. TANK TO BE BUILT & LABELED PER U.L. SPEC. #142.
- TANK TO BEAR MANUFACTURERS & U.L. LABELS ONLY. E.
- TANK TO BE AIR TESTED WITH WATER & SOAP SUDS SOLUTION.
- INTERIOR: REMOVE WELD SLAG (SHIP CLEAN & DRY).
- EXTERIOR: GRAY PRIMER INCLUDED; SEE SALES ORDER FOR TOP COAT.
- ALL FITTINGS TO BE PROTECTED FOR SHIPMENT.
- CUSTOMER HAS THE RESPONSIBILITY TO VERIFY ALL DIMENSIONS.

APPROVAL FOR CONSTRUCTION SCHEDULE A - MASTER TERMS & CONDITION OF SALE*	
CONDITION OF SALE	

## APPROVED AS DRAWN.

APPROVED WITH NOTED CHANGES, CONSTRUCTION WILL BE SCHEDULED WHEN SIGNED DRAWING AND CONFIRMED ORDER ARE RECEIVED.

\*All pages of this Schedule A are incorporated by reference and are a part of the additional terms of the Master Terms & Conditions of Sale. www.newberrytanks.com/masterterms.pdf

## SALES ORDER: -Newberry Tanks

DESCRIPTION:

**New Thinking** 

All units inches

unless stated

CHKD BY:

Phone: 870-735-4473

220 GALLON RECTANGULAR UL 142 SINGLE WALL TANK

CUSTOMER P.O.# DATE: 2/8/2023 DWG.# FTSBSW-0220 DRAWN BY