





	NOZZLE SCHEDULE							
ITEM	SIZE	RATING	TYPE	MATL	PROJ IN	PROJ OUT	REMARKS	
Α	6''	N.P.T.	H.CPL.	C.S.	STD.	STD.	EMERGENCY VENT OPENING	
В	2''	N.P.T.	W.F.	C.S.	STD.	STD.		
С	3/4"	N.P.T.	W.F.	C.S.	STD.	STD.	DRAIN	









NOTES:

MATERIAL: H.R. CARBON STEEL

DESIGN & OPERATING PRESSURE: ATMOSPHERIC.

DESIGN & OPERATING TEMPERATURE: AMBIENT.

TANK TO BE BUILT & LABELED PER U.L. SPEC. #142. D.

TANK TO BEAR MANUFACTURERS & U.L. LABELS ONLY. E.

TANK TO BE AIR TESTED WITH WATER & SOAP SUDS SOLUTION.

INTERIOR: REMOVE WELD SLAG (SHIP CLEAN & DRY).

EXTERIOR: GRAY PRIMER INCLUDED; SEE SALES ORDER FOR TOP COAT. ALL FITTINGS TO BE PROTECTED FOR SHIPMENT.

CUSTOMER HAS THE RESPONSIBILITY TO VERIFY ALL DIMENSIONS.

APPROVAL FOR CONSTRUCTION SCHEDULE A - MASTER TERMS & CONDITION OF SALE*

APPROVED AS DRAWN.

APPROVED WITH NOTED CHANGES, CONSTRUCTION WILL BE SCHEDULED WHEN SIGNED DRAWING AND CONFIRMED ORDER ARE RECEIVED.

*All pages of this Schedule A are incorporated by reference and are a part of the additional terms of the Master Terms & Conditions of Sale. www.newberrytanks.com/masterterms.pdf Newberry Tanks **New Thinking**

DESCRIPTION:

All units inches unless stated

Phone: 870-735-4473

1000 GALLON RECTANGULAR UL 142 SINGLE WALL TANK CUSTOMER

DATE: 2/8/2023 DWG.# FTSBSW-1000 DRAWN BY CHKD BY: